



STANDARD SYMBOL

A-2 / B-3

504

CONSTRUCTION SPECIFICATIONS

NO SCALE

NOTES

- 1. ALL TEMPORARY SWALES SHALL HAVE UNINTERRUPTED POSITIVE GRADE TO AN OUTLET.
- 2. DIVERTED RUNOFF FROM A DISTURBED AREA SHALL BE CONVEYED TO A SEDIMENT TRAPPING DEVICE.
- 3. DIVERTED RUNOFF FROM A UNDISTURBED AREA SHALL OUTLET DIRECTLY INTO AN UNDISTURBED STABILIZED AREA AT NON-EROSIVE VELOCITY.
- 4. ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS, AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED AND DISPOSED OF SO AS NOT TO INTERFERE WITH THE PROPER FUNCTIONING OF THE SWALE.
- 5. THE SWALE SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE, AND CROSS SECTION AS REQUIRED TO MEET THE CRITERIA SPECIFIED HEREIN AND BE FREE OF BANK PROJECTIONS OR OTHER IRREGULARITIES WHICH WILL IMPEDE NORMAL FLOW.
- 6. FILLS SHALL BE COMPACTED BY EARTH MOVING EQUIPMENT.
- 7. ALL EARTH REMOVED AND NOT NEEDED ON CONSTRUCTION SHALL BE PLACED SO THAT IT WILL NOT INTERFERE WITH THE FUNCTIONING OF THE SWALE.
- 8. STABILIZATION SHALL BE AS PER THE CHART BELOW:

FLOW CHANNEL STABILIZATION

TYPE OF TREATMENT	CHANNEL GRADE	A (5 AC OR LESS)	B (5 AC - 10 AC)		
1	0.5% - 3.0%	SEED AND STRAW MULCH	SEED AND STRAW MULCH		
2	3.1% - 5.0%	SEED AND STRAW MULCH	SEED USING JUTE OR EXCELSIOR		
3	5.1% - 8.0%	SEED WITH JUTE OR EXCELSIOR; SOD	LINED RIP-RAP 4-8' RECYCLED CONCRETE EQUIVALENT		
4	8.1% - 20.0%	LINED 4-8' RIP-RAP	ENGINEERED DESIGN		

9. PERIODIC INSPECTION AND REQUIRED MAINTENANCE MUST BE PROVIDED AFTER EACH RAIN EVENT.

TEMPORARY SWALE

NO SCALE

	JON C. SPANGLER	N DFM		STAND	ARD DETAILS	
APPROVED: _	SEPT. 1, 1995	THE C. THOMES	TEMPORARY SWALI			LE
STORMWATER DIVISION		30HINGTON	FILE	SD504.DWG	DRAWING NO	٥.